



Institute Works Department

Ref. No.: IIT(BHU)/IWD/CT/44/Rajputana/2017-18/1191

Dated: 30 August, 2017

QUOTATION NOTICE


1. Quotation are invited from **enlisted 'B'** class contractors of UWD BHU for **construction of RCC covered drain along with Basketball Court at the Rajputana Ground, IIT(BHU), Varanasi,** Varanasi as per description below. The sealed envelope containing quotation shall be superscripted with the name of the work, tender enquiry ref. no. & date. The quotations will be received up to **3:00 P.M on or before 12.09.2017** in the office of Chairman, Institute Works Department, IIT(BHU), Varanasi.

S. N.	Description of Items	Qty.		Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m				
	All kinds of soil. (2.8.1)	161.00	cum		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work upto plinth level				
	1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) (4.1.8)	13.00	cum		
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in :				
	Cement mortar 1:6 (1 cement : 6 coarse sand) (6.1.2)	34.00	cum		



Institute Works Department


4	Providing and placing in position 100mm thick factory made machine batched & machine mixed Precast RCC Rectangular Covers on drains of footpath of various sizes, of M-25 grade cement concrete for RCC work, including cost of centering, shuttering, reinforcement of 8mm dia TMT bars of Fe 500 grade @ maximum 100mm c/c on both ways, neat cement punning on finished surface, properly encased on all edges with 1.6 mm thick, 100mm wide MS sheet duly painted over priming coat, reinforcement to be welded at edges with MS sheet and providing 2 Nos. 12 mm dia bar for hooks etc i/c cost of cartage, all leads & lift, handling at site etc. all complete as per direction of Engineer-in-Charge. (16.93)	75.00	Sqm		
5	Providing and laying Non Pressure NP-3 class (Medium duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 450 mm dia RCC pipes. (19.35.1)	124.00	mtr		
6	Constructing brick masonry road gully chamber 50x45x60 cm with bricks of class designation 75 in cement mortar 1:4 (1 cement : 4 coarse sand) including 500x450mm pre-cast R.C.C. horizontal grating with frame complete as per standard design: With common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (19.27.1)	4	nos		
7	Constructing brick masonry road gully chamber 110x50x77.5 cm with bricks of class designation 75 in cement mortar 1:4 (1 cement : 4 coarse sand) including 500x450 mm precast R.C.C. horizontal grating with frame and vertical grating complete as per standard design With common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (19.29.1)	5	nos		
8	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement : 4 fine sand) (13.7.2)	180.00	Sqm		



Institute Works Department

9	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth: consolidating each deposited layer by ramming and watering, lead up to 50m and lift up to 1.5m. (2.25)	106.00	cum		
10	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead upto 50 m and lift upto 1.5 m.				
	All kinds of soil (2.28.1)	517.00	Sqm		
11	Carrage of Malba. (Approved Rate)	20	Trip		
Total Amount ₹					
Amount in word ₹					

- All distempering/painting work will be verified by a combined committee of IWD engineers and users of above mentioned work as per following 4 stages:
 - After Scrapping stage.
 - After Water thinable priming coat stage.
 - After Distempering 1st coat stage.
 - After Distempering 2nd coat stage.
- The quotation forms complete in all aspects should be submitted in sealed envelope along with tender fee of ₹ 500/- in the form of demand draft drawn in favour of the Registrar, IIT (BHU), payable at Varanasi.
- The estimated cost of this work is ₹ 7,16,813.00 The earnest money deposit of ₹ 14,500/- shall be submitted in the form of FDR or DD in favour of the Registrar, IIT (BHU), payable at Varanasi. The EMD of successful bidder will be retained till the completion of work and shall be returned after the payment of final bill & deduction of security. The EMD of unsuccessful bidders shall be returned after the final award of work.
- In case one or more eligible bidders are found lowest that is the L-1 prices are same then all L-1 bidders will be asked to resubmit their bids in sealed envelop with the objective to break the tie cases and determine a single L-1 bidder.
- The works will be executed on Agreement/work order basis.



Institute Works Department

7. Institute reserves the right to reject any quotation or all quotation without prejudice, assigning any reason or giving any explanation.
8. If quotation are submitted without clearly writing the rates then quotation will not be considered.
9. Quotation not signed by the contractor or his legally authorized agent will be considered invalid.
10. **Security deposit @ 5%** shall be deducted from each bill. The security deposit of 5% deducted from all the bills will be refunded after completion of the defect liability period i.e. 6 months from the date of works completion. The date of issue of work completion certificate will be treated as the work completion date.
11. 1% water tax will be deducted from each bill, wherever applicable.
12. Electricity charge will deducted as per actual consumption.
13. 2% Income Tax and other applicable taxes such as GST etc. shall be deducted as per applicable Govt. rules.
14. **Amount and quantity variation:** Quantity may vary as per actual work execution/site requirement/end user suggested changes during execution but the final bill value shall not exceed more than 5% of order value.
15. **Work completion period:** Within 60 days from the issue of work order/date of agreement. Work completion certificate shall be issued by the IWD after obtaining a satisfactory work done report from the user. A period of 10 days will be added to the work completion period for completion of above procedure.
16. **Late work completion penalty:** If work in not completed within the given time, penalty will be deducted as per institute norms.
17. Any damage caused to the building shall have to be made good by contractor at no extra cost & without any delay.
18. Duly completed tender document alongwith Quotation form, tender fee & E.M.D. should be sealed in one Envelop which should be superscribed with Name of work, Tender Reference No. & date submitted on or before the last date & time as mentioned at S. No. 1 above.
19. The bids submitted after the last date & time will not be considered for opening. The bids received within the last date & time will be opened on 12.09.2017 at 4:00 P.M. in the Committee room (Ground Floor) of the Administrative Building, IIT (BHU), Varanasi.


Dy. Registrar & Member Secretary
IWC, IIT (BHU),
Varanasi

QUOTATION FORM

*The Chairman (IWC),
Institute Works Department
Indian Institute of Technology (BHU)
Varanasi - 221005*

Sub: Quotation for _____

Dear Sir,

With reference to the Quotation invited by you for the captioned work. I/We do hereby offer to perform, provide, execute, complete and maintain work in conformity with the drawing, conditions of tender, articles of agreement conditions of contract, specification and quantities of the sum of Rs. _____

(Rupees _____
_____) at the respective rates mentioned in the quotations.

My/Our quotation will remain open for acceptance for 12 months from the date of its opening.

Yours faithfully,

Date: _____

(Signature of contractor with seal)