



Institute Works Department

Ref. No.: IIT(BHU)/IWD/C/37/Various Hostel/2016-17/620

Dated: 30 August, 2016

QUOTATION NOTICE

1. Quotation are invited from **enlisted 'A'** class contractors of UWD BHU for *construction of cycle stand in Vivekanand, S.C. De, Limbdi, Rajputana, G.S.M.C new Hostel, Morvi, C.V.Raman, S.N.Bose & S.Ramanujan Hostels of IIT(BHU)* as per description below. The sealed envelope containing quotation shall be superscribed with the name of the work, tender enquiry ref. no. & date. The quotations will be received up to **3:00 P.M on or before 15.09.2016** in the office of Chairman, Institute Works Department, IIT(BHU).

Sl. No	Description of Item with measurements	Quantity		Rate	Unit	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m					
	All kinds of soil. (2.8.1)	65.00	Cum		cum	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work upto plinth level					
	1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)(4.1.10)	28.00	Cum		Cum	
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in :					
	Cement mortar 1:6 (1 cement : 6 coarse sand) (6.1.2)	80.00	Cum		Cum	
4	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth: consolidating each deposited layer by ramming and watering, lead up to 50m and lift up to 1.5m. (2.25)	65.00	Cum		Cum	



Institute Works Department

5	Providing and laying factory made coloured chamfered edge Cement Concrete paver blocks of required strength, thickness & size/shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of fine sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with jamuna sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand in footpath, parks, lawns, drive ways or light traffic parking etc. complete as per manufacturer's specifications & direction of Engineer-in-Charge. 60mm thick C.C. paver block of M-35 grade with approved colour, design & pattern.(16.91)	2295.00	Sqm		Sqm
6	Cement plaster 1:3 (1 cement: 3 coarse sand) finished with a floating coat of neat cement				
	12 mm cement plaster (13.9.1)	320.00	Sqm		Sqm
7	Supplying and filling in plinth with Jamuna sand under floors, including watering, ramming, consolidating and dressing complete.(2.27)	10.00	cum		cum
8	Carrage of Malba. (Approved Rate)	50.00	Trip		Trip
Total Rs.					

- The quotation forms complete in all aspects should be submitted in sealed envelope along with tender fee of Rs. 500/- in the form of demand draft drawn in favour of the Registrar, IIT (BHU), payable at Varanasi.
- The estimated cost of this work is Rs. 21,98,536.66. The **earnest money deposit** of Rs. 44,000/- shall be submitted in the form of FDR or DD in favour of the Registrar, IIT (BHU), payable at Varanasi. The **EMD** of successful bidder will be retained till the completion of work and shall be returned after the payment of final bill & deduction of security. The EMD of unsuccessful bidders shall be returned after the final award of work.



Institute Works Department

4. The works will be executed on Agreement/work order basis.
5. Institute reserves the right to reject any quotation or all quotation without prejudice, assigning any reason or giving any explanation.
6. If quotation are submitted without clearly writing the rates then quotation will not be considered.
7. Quotation not signed by the contractor or his legally authorized agent will be considered invalid.
8. **Security deposit @ 5%** shall be deducted from each bill. The security deposit of 5% deducted from all the bills will be refunded after completion of the defect liability period i.e. 6 months from the date of works completion. The date of issue of work completion certificate will be treated as the work completion date.
9. 1% water tax will be deducted from each bill, wherever applicable.
10. Electricity charge will deducted as per actual consumption.
11. 5% Trade tax and 2% Income Tax will be deducted from each bill.
12. **Amount and quantity variation:** Quantity may vary as per actual work execution/site requirement/end user suggested changes during execution but the final bill value shall not exceed more than 5% of order value.
13. **Work completion period:** Within 90 days from the issue of work order/date of agreement. Work completion certificate shall be issued by the IWD after obtaining a satisfactory work done report from the user. A period of 10 days will be added to the work completion period for completion of above procedure. If work is not completed as per given time penalty should be charged as per institute norms.
14. **Late work completion penalty:** If work in not completed within the given time, penalty will be deducted as per institute norms.
15. Any damage caused to the building shall have to be made good by contractor at no extra cost & without any delay.


Dy. Registrar & Member Secretary
IWC, IIT (BHU),
Varanasi