



Institute Works Department

Ref. No.: IIT(BHU)/IWD/C/38/ Rajputana Ground /2016-17/621

Dated: 30th August, 2016

QUOTATION NOTICE (RETENDER)

1. Quotation are again invited from **enlisted 'A' & 'B'** class contractors of UWD BHU for **construction of Storm Water Drain Around the Rajputana Ground ,IIT (BHU)**. as per description below. The sealed envelope containing quotation shall be superscribed with the name of the work, tender enquiry ref. no. & date. The quotations will be received up to **3:00 P.M on or before 15.09.2016** in the office of Chairman, Institute Works Department, IIT(BHU). Those enlisted A & B class contractors who have already submitted their bid in response to our tender inquiry no. IIT(BHU)/IWD/C/33/ Rajputana Ground /2016-17/350 dated 29.06.2016 need not submit fresh bids as their earlier submitted bid will be considered. However, if they wish to revise their bids they may submit fresh bids. The tender fee and EMD submitted vide their earlier bid will be considered for this bid. However, they have to revalidate their drafts of tender fee & EMD if their validity expires. This retendering is being done because only one bid was received in response to earlier quotation enquiry.


S. N.	Description of Items	Qty.	Rate	Unit	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m				
	All kinds of soil.(2.8.1)	897.00	Cum	Cum	
2	Brick on edge flooring with bricks of class designation 75 on a bed of 12mm cement mortar, including filling the joints with same mortar, with common burnt clay non modular bricks:				
	1:4 (1 cement : 4 coarse sand) (11.1.1)	382.00	Sqm	Sqm	
3	Dry brick pitching half brick thick in drains including supply of bricks and				
	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (16.12.1)	2075.00	Sqm	Sqm	
4	Deduction of Rate for dry brick pitching (for Item No. 03) (Analysed Rate)	2075	Sqm	Sqm	
5	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth: consolidating each deposited layer by ramming and watering, lead up to 50m and lift up to 1.5m. (2.25)	180	Cum	Cum	
6	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead upto 50 m and lift upto 1.5m :				
	All kinds of soil. (2.28.1)	5000	Sqm	100 Sqm	



Institute Works Department

7	Carrriage of Melba (Approved Rate)	120	Trip	Trip	Total Rs.

- The quotation forms complete in all aspects should be submitted in sealed envelope along with tender fee of Rs. 500/- in the form of demand draft drawn in favour of the Registrar, IIT (BHU), payable at Varanasi.
- The estimated cost of this work is Rs. 11,55,961.29. The **earnest money deposit** of Rs. 23,500/- shall be submitted in the form of FDR or DD in favour of the Registrar, IIT (BHU), payable at Varanasi. The **EMD** of successful bidder will be retained till the completion of work and shall be returned after the payment of final bill & deduction of security. The EMD of unsuccessful bidders shall be returned after the final award of work.
- The works will be executed on Agreement/work order basis.
- Institute reserves the right to reject any quotation or all quotation without prejudice, assigning any reason or giving any explanation.
- If quotation are submitted without clearly writing the rates then quotation will not be considered.
- Quotation not signed by the contractor or his legally authorized agent will be considered invalid.
- Security deposit @ 5%** shall be deducted from each bill. The security deposit of 5% deducted from all the bills will be refunded after completion of the defect liability period i.e. 6 months from the date of works completion. The date of issue of work completion certificate will be treated as the work completion date.
- 1% water tax will be deducted from each bill, wherever applicable.
- Electricity charge will deducted as per actual consumption.
- 5% Trade tax and 2% Income Tax will be deducted from each bill.
- Amount and quantity variation:** Quantity may vary as per actual work execution/site requirement/end user suggested changes during execution but the final bill value shall not exceed more than 5% of order value.
- Work completion period:** Within 60 days from the issue of work order/date of agreement. Work completion certificate shall be issued by the IWD after obtaining a satisfactory work done report from the user. A period of 10 days will be added to the work completion period for completion of above procedure.
- Late work completion penalty:** If work in not completed within the given time, penalty will be deducted as per institute norms.
- Any damage caused to the building shall have to be made good by contractor at no extra cost & without any delay.


Dy. Registrar & Member Secretary
IWC, IIT (BHU),
Varanasi